

An Estimate of the carpenters work of the Barracks proposed to be erected by Government in the fuel yard near Fort Howe to be 101 feet long by 38 feet wide.

The Building to be framed and raised.

The Partition Stairs to be set up.

The cellar sleepers to be laid.

The ceiling joists to be put up in the upper story.

A good Base and Plinth to be put round the Building out sides.

The four Corners to be Rusticated.

Fifty two Sash frames to be made and set with sashes for each.

Single narrow siding to be planed, rabbeted, beaded, and put up. x

A good dentil cornice to be put up, round out side the Building.

The Roof to be laid with two Inch pine Planks, tined, prepared, and sanded.

The Kitchen floors to be planed, jointed & laid with Inch & half pine Planks.

The two next floors to be planed, jointed, tongued, grooved, & laid with ³/₄ Inch pine Planks.

Twenty eight Door Jambs to be made and set.

Twenty wainscot Doors to be made & fitted in, such on both sides & raised on one.

Eight plain battened Doors to be made for Kitchens.

Thirty six floor or Cupboards to be made in the Building with plain battened Doors. x

Single faced Architraves to be put round all the Doors and Windows.

Four Rooms for Officers to have Base & cornice put round each. x

Four four places to be finished with Architraves, frieze, and Cornice. x

Four Stories of Stairs to be finished.

Steps and Platform to each of the out side Doors to be made.

Ten Condents to be made and put up.

Wash boards to be put round all the Rooms Passages and Kitchens.

Four Gothic sashes to be made & put up, one over each out side Door. x

Hinges, locks, Bolts & fastenings to be put on in all the Building.

Birch to be put up in twelve Rooms, to hold sixteen men in each Room.

Three sides of the fence inclosing the Yard, to be planed on both sides, jointed,

spring, and put up eight feet high, the front to be put up with Rails &

Balusters agreeable to the Plan.